

Standard Features:

- Easily mounts in standard class III or higher 2" receivers.
- Requires no modifications to truck.
- Magnet is activated or deactivated by a simple lever rotation.
- Manual hand brake winch with a lifting hook and 15 feet of cable is included.
- Offset design allows for full use of tailgate while winch is in operation.
- Crane may be installed on either side of the truck bed.
- Tough, baked-in powder coated finish.
- Durable steel construction.



Magnets Activated/Deactivated by Simple Lever Rotation





Mounts in Standard Class III or Higher 2" Receivers

MODEL NUMBER	OVERALL SIZE (W x L x H)	BOOM REACH	MAXIMUM BOOM HEIGHT	MAGNET LIFTING CAPACITY	WEIGHT (LB)
WTJ-HITCH-ML-2	19 ^{13/} 16" x 44½" x 84%"	471⁄2	84%"	200 lb.	168
WTJ-HITCH-ML-6	19 ^{13/} 16" x 44½" x 84%"	471⁄2	84%"	600 lb.	168

Also available in a standard hook model, WTJ-HITCH.



Vestil Manufacturing Corporation Larissa Flora - Sales Representative

2999 North Wayne Street, P.O. Box 570 Angola, Indiana 46703, USA Phone: (260) 624-4341 Fax: (260) 665-1339 E-Mail: larissa@vestil.com Web: www.vestil.com